Notice dated 6th November 1918.

Tenders from building contractors are invited by the undersigned for altering and extending the Public Works Dispensary at Bethamangala up to 11 A.M., 21st November 1918.

The estimated quantities of the items of work are given in the memo annexed below and the approved plan itself can be seen in the undersigned's office on all week days during office hours and the work has to be completed in one month's time.

Each tender must give the rates at which the different items of work will be carried out; it should be submitted in sealed covers superscribed "Tenders for extending the Public Works Dispensary at Bethamangala" and also accompanied by a deposit of Rs. 50 only in cash or Government currency notes as earnest money failing which it will not be received.

The final acceptance of the tender rests with the Executive Engineer, Water-Supply Division, Bangalore, who does not bind himself to accept the lowest or any tender.

On acceptance of one of the tenders the earnest money on the others will be returned on application.

Within eight days of intimation of acceptance the successful contractor should execute the usual mutchalika failing which the same will be cancelled and his earnest money forfeited to Government.

Memo.

Items of work	Per	Quantity
Earthwork excavation for foundation and filling basement	C. yds.	13
Burnt stone in chunam	C. ft.	434
Burnt brick in clay	"	515
Burnt brick in chunam	"	60
Burnt stone slabs 4" thick	S. ft.	47
Do 6" thick	"	14
Teakwood work wrought and put up complete including wood oiling ..	C. ft.	21·33
Roofing with 1st class Mangalore tiles and teak reepers	Sq.	4·00
Ridge tiles set in mortar	S. ft.	11½
Teakwood panelled doors including iron work complete	"	23
Teakwood panelled windows with glazed shutters and iron bars, etc. ...	"	24
Chunam pointing	Sq.	·49
Chunam plastering	"	10·88
Flooring with Mangalore square tiles on 3" concrete and cement pointing ...	"	1·80
Flooring with Cuddappa slabs on 3" concrete and cement pointing	"	·47
White and colourwashing	"	10·88
Wood oiling painting and other sundry works required	"	Lump sum
Dismantling masonry	C. ft.	520
Removing and refixing doors and windows masonry works and other sundry works.	"	Lump sum

S. SRINIVASA AIYAR,
Executive Engineer.

HEADQUARTER RANGE, MYSORE.

Notice dated 30th October 1918.

Notice is hereby given that sealed tenders will be received at the office of the Assistant Engineer, Headquarter Range, Mysore, up to the 23rd November 1918, for constructing the South Fort Gate with wings at Mysore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1919.

2. Tenders should be submitted on printed forms which may be obtained from the Assistant Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

3. Tenders containing indefinite remarks against the rates for items such as "as per estimate" "as per market rate" "as per data" and "departmental supply, etc," will not be considered. Specific rates for all items except lump sum ones must be entered in the tenders.

4. The tenders must be accompanied by a deposit of rupees five hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing the South Fort Gate with wings at Mysore", in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Assistant Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract of detailed quantities for constructing the South Fort Gate with wings at Mysore.

Item No.	Particulars	Per	Quantity
	Constructing South Gate of Fort—		
1	Earthwork excavation	C. yd.	237
2	Filling concrete foundation	C. ft.	2,560
3	Size stone in mortar foundation	„	2,724
4	Do in basement	„	1,007
5	Chamundi stone coping slabs of basement with moulding	„	212
6	Brick in mortar superstructure	„	6,544
7	Chamundi stone foliated arch	„	179
8	Arch work brick in chunam foliated	„	122
9	Wire cut brick in mortar	„	823
10	Ornamental Chamundi stone pendents	„	245
11	Bearing slabs of girders	S. ft.	59
12	Chamundi stone lovey brackets with plaster ornamentations	No.	102
13	Chamundi stone belt coursed slabs	S. ft.	195
14	Cuddappah slabs lovey including plaster, etc., complete	„	912
15	Ornamental square octogonal turrets with finials, etc., complete	No.	8
16	Ornamental masonry vimanums including with masonry plastering with finials, etc.	„	2
17	Ornamental parapet big and small of balustraded with pedestals, complete	R. ft.	127
18	Ornamental Turuvekere brackets for lovey	No.	16
19	Chamundi stone slabs over brakets with moulding at edges below	S. ft.	72
20	Ornamental circular pillars of pot stones or Turuvekere with base and capitals.	No.	16
21	Chamundi stone bressummer dressed	R. ft.	56
22	Masonry spandrils and foliated arches for balcony	Sq.	80
23	Cuddappah slab lovey for balcony	S. ft.	58
24	Ornamental terrace brick masonry dome with freize moulding and finials, etc., complete.	No.	4
25	Ornamental parapet wall, complete	R. ft.	36
26	Steel girders and steel joists	Cwt.	47
27	Flat terrace, pukka	Sq.	4·75
28	Segmental valting of 3 rings of terrace brick in mortar including the cost of centring.	„	3·68
29	Ceiling decorations of stucco work moulding painting, etc., complete	S. ft.	659
30	Chunam plastering	Sq.	81·40
31	Cement pointing	„	6·13
32	Ornamental cornice below lovey	R. ft.	150
33	Cornice inside	„	168
34	Archivolts or string course	„	209
35	Forming pillars with case and capitals	No.	16
36	Enriching the spandrils and pillars	S. ft.	579
37	Beading alround the panelling	R. ft.	940
38	Boxing girders with fero concrete plastering decorations, etc., complete	S. ft.	62
39	White and colourwashing	Sq.	81·40
40	Gilded finials at corners	No.	8
41	Do over vimanums	„	2
42	Cuddappah slabs flooring over 3" concrete with cement pointing	Sq.	2·77
43	Forming earth gravelling, etc, complete	Lump	sum Rs.
44	Forming bottom and top of pillars of the side bay passage	Each	8
45	Rosetts in haunches of side bay passage	„	8
46	Ornamental cresting over side bay passage	„	4
	Constructing arcaded wall adjacent to South Fort Gate, Mysore—		
1	Earthwork excavation	C. yd.	162
2	Concrete for foundation	C. ft.	1,459
3	Burnt size stone in chunam for foundation	„	1,870
4	Do in basement	„	790
5	Brick in chunam for superstructure	„	3,299
6	Foliated arch work	„	295
7	Plastering in chunam	Sq.	54·02
8	Burnt stone slabs 6" thick roughly dressed	S. ft.	615
9	Chamundi stone lovey bracket with plaster ornamentation	R. ft.	162
10	Cuddappah slabs lovey including plaster, etc., complete	S. ft.	350
11	Masonry parapet wall with perforated work in mortar	R. ft.	142
12	Beading below lovey cornice as per above masonry parapet wall with perforated work in mortar.	„	142
13	Archivolts of arches	„	50
14	Forming bottom and capitals of pillaster of archway	Each	16
15	Ornamental crestal over archway	„	20
16	Rosetts 1½" projection in haunches of archway	„	8
17	Enriching the spandrils of archway	S. ft.	56
18	Ornamental perforated wire parapet wall with brackets, etc., complete	R. ft.	96
19	Cutting stone cornice	„	120
20	Moulding bottom of tower in cement	„	190
21	Dismantling existing tower to the required level of the proposed wall and re-building the same.	Lump	sum Rs.
22	Constructing masonry ornamental parapet wall to the staircase outside	R. ft.	108
23	Masonry turrets over octogonal towers in rear side, complete	Each	6
24	Ornamental circular pillars of pot stone or Thuruvekere with base and capital.	„	16
25	Chamundi stone bressumers 4"×6"	R. ft.	72
26	Masonry spandrils and foliated arch for tower	S. ft.	288
27	Cuddappah slabs lovey for tower with brackets	R. ft.	88
28	Ornamental parapet wall at the necky dome	„	72
29	Ornamental terrace brick masonry dome with frieze moulding, etc., complete, plastering with scaffolding.	C. ft.	229
30	Cement pointing to basement	Sqr.	7·56
31	Gilded finials, complete	Each	2

GURU RAO SIRSI,
Assistant Engineer,
Headquarter Range, Mysore.